1 [redacted] FLOOR PLAN - AREA B

1/8" = 1'-0"

GENERAL NOTES:

A. COORDINATE ALL SPRINKLER MAINS, BRANCHES AND HEAD LOCATIONS WITH ALL OTHER TRADES.

B. THE CONTRACTOR SHALL HYDRAULICALLY CALCULATE ALL SPRINKLER SYSTEMS AND SHALL SIZE THE PIPING ACCORDINGLY.

C. PROVIDE FULL SPRINKLER COVERAGE FOR ALL CONCEALED SPACES PER NFPA 13.

D. PROVIDE SPRINKLER HEAD UNDER ALL FIXED OBSTRUCTIONS WIDER THAN 4'-0" PER NFPA.

E. PROVIDE SPRINKLER HEAD(S) OFF THE DRY SYSTEM WHERE TEMPERATURE DROPS BELOW 40 DEGREES.

DRAWING NOTES:

1 THIS ROOM SHALL BE PROTECTED BY A CLEAN AGENT SYSTEM. REFER TO DRAWING FP-109.

NOT FOR CONSTRUCTION



KEY PLAN

beardsley
architects + engineers

AUBURN
64 South Street
Auburn, NY 13021
315.253.7301

MALONE
320 West Main Street
Malone, NY 12953
518.483.1585

SYRACUSE
5789 Widewaters Pkwy
Dewitt, NY 13214
315.472.6980

EC4B engineering, p.c.
15 Schoen Place
Suite 300
Pittsford, NY 14534
Phone: (585) 641-7121
Fax: (585) 362-4175
www.ec4b.com

OF THE IGA BUILDING
k Tribe
gansburg, NY 13655

WARNING
Any alterations to this document not conforming to section 7307, New York State Education Law are strictly prohibited.

[redacted]

2/11/2022

Project [redacted]

Drawn [redacted]

Designed [redacted]

Reviewed By: NMG

no.	revision description	by	date

[redacted] FLOOR PLAN - AREA B

FP-106

Beardsley Design Associates [redacted] Landscape [redacted] D.P.C. ©

Filename C:\Users\jsappeteli\Documents\137159 - IGA SRMT MEP Central_jsappeteli.rvt

2/11/2022 3:35:41 PM